SKILL SEWA

Service at your doorstep

CONTRACT AGREEMENT

CLIENT'S NAME : Mrs. Radhika K.C. Khadka

CONTRACT DATE : 2082/12/23

हामी दुवै पक्ष्य तल भनिएका बुदाँहरु मान्न तयार छौँ।

सम्झौतामा संलग्न बुंदाहरु यसप्रकार छन् :

- हामी मापदण्ड अनुसार निर्माण कार्य गर्न सहमत छौं र अनुमानमा उल्लेख गरिएका क्षेत्रहरूमा मात्र काम गर्नेछौं ।
- अनुबंधित लागत अनुमानमा उल्लेख बाहेकका कार्यहरूको दायरा थप निर्माण कार्यको लागि पुनः अनुमानित हुनुपर्छ ।
- प्लम्बिङ, सेनेटरी, टाइलिङ, पेन्टिङ र Interior सम्बन्धी कार्य अनुमानका आधारमा तय गरी सोही अनुसार अघि बढाइनेछ ।
- ग्राहकहरूलाई कुनै पनि परिस्थितिमा अतिरिक्त कामको लागि **पहिलो पक्ष्यले** प्राविधिकहरूलाई जबरजस्ती / बाध्य पार्न अनुमति हुने छैन । सहमतिमा BOQ मा उल्लेखित दरमा सम्बन्धित कार्य थपघट गर्न सकिनेछ ।
- निर्माण अवधिमा डिजाइनमा कुनै परिमार्जन भएमा, डिजाइनमा परिमार्जनले लागतमा प्रभाव पार्ने रूपमा लागत पुनः अनुमान गरिनेछ ।
- दुवै पक्षबाट निर्णय निर्माताहरू सम्झौतामा उल्लेख बाहेक परिस्थितिमा विशिष्ट व्यक्ति द्वारा प्रमाणित गरिनेछ ।
- सबै सामग्री Design अनुसारको कार्यमा प्रयोग गरिनेछ । अन्यथा **पहिलो पक्ष्यले** जिम्मेवार हुनेछ।
- दुवै पक्षको पहुँचमा आपसी समझदारीमा सीसी क्यामेरा जडान गरिनेछ ।
- क्याम्प सेटअप गर्न आवश्यक छ जसको लागि क्याम्पको लागि जग्गा व्यवस्थापन गर्न ग्राहकले ठाउँ उपलब्ध गर्नुपर्नेछ ।
- सामग्रीको बजार मूल्य (+/-१०%) मा उतार-चढावले अनुमानलाई असर गर्नेछ र अन्तिम बिलिङमा बजार मूल्य अनुसार गणना गरिनेछ ।
- निर्माणको लागि ग्राहकले पानी, **बिजुली र ईन्टरनेटको** उपलब्ध **गराउनुपर्नेछ** I
- ग्राहकले सामग्री डम्पिङ र काम गर्ने उद्देश्यका लागि उपयुक्त ठाउँ **र बाटो** उपलब्ध गराउनुपर्छ ।
- वारेन्टी प्रावधानः सम्झौताहरूले ५ वर्षको लागि संरचनात्मक भाग (सिपेज, पानी चुहावट, सर्ट सर्किट) मा आधारभूत सेवा वारेन्टी प्रदान गर्नेछ ।
- **जग्गा तथा छिमेकिको समस्याको जिम्मा दोस्रो पक्ष्यले लिनेछ**, **जसमा पहिलो पक्ष्यले** technical **सहयोग गर्छ।**
- contract **पछि** design change **हुदा** cost estimation change **हुन्छ।**
- निर्माण लागत अनुमानमा प्रयोग गरिएको निर्माण सामग्रीको प्रयोग गरिनेछ ।
- ***Plumbing and Sanitary*** सामान को खरिदमा दुइ पक्षको सम्झौता अनुरुप थप घट गर्न सकिने छ ।
- हरेक जिज्ञासाहरुको इञ्जिनियरिङ्ग/टेक्निकल सिद्धान्त, अनुभव, प्रचलित परिवेश आधारमा सन्तुष्ट गराईनेछ ।
- **बाटो देखि जति फीट तल जग्गा छ**, **दोस्रो पक्ष्यले बाटो सम्म आउनको लागि प्रति फीट १ लाख रुपीयाको दरले तिर्नु पर्ने हुन्छ**,
- निर्माणको हरेक कार्यहरु (Structural, electrical wiring, plumbing, sanitation, waterproofing etc.) सम्बन्धित विज्ञ, प्राविधिकको निगरानी र उपस्थितिमा हुनेछ ।
- प्रचलित मापदण्ड, सम्झौतामा उल्लेखित Design, Drawing, Specification) मापदण्ड विपरित तथा स्किल सेवाले नियतवश अनुचित लाभ हुनेगरी unethical कार्य गरेमा आपसी समझदारीमा सम्झौता भंग गर्न सकिनेछ ।
- Contract **मा लेखिएको कार्यमा मात्र मान्यता दिइनेछ**, **मौखिक सहमती भएको कार्यलाई दिईदैन** ।

- कार्य सुरु भए देखि हस्तान्तरण सम्मको अवधिभर कर्मचारी, कामदार, तथा निर्माणसंग सम्बन्धित कार्यको योग्यता, विज्ञता, अनुभव भएको प्राविधिकबाट सफल भएको परिक्षण, प्रमाणित हुनु अनिवार्य छ ।
- भुक्तानी तालिका अनुसार भुक्तानी हुनेछ । प्रत्यक खण्डको भुक्तानीको लागि **पहिलो पक्ष्यले** तथा सम्बन्धित कार्यको योग्यता, विज्ञता, अनुभव भएको प्राविधिकबाट सफल भएको प्रमाणित हुनु अनिवार्य छ ।
- निर्माण कार्यको कुनै पनि चरणमा ग्राहक वा निजको प्रतिनिधि उपस्थित भई निर्माण कार्यको गुणस्तर परिक्षण, निरीक्षण, गरी **पहिलो पक्ष्यले**संग जिज्ञासा राख्न सकिनेछ ।
- **स्किल सेवाले** management, engineering, **र** financial, planning, quality **र** time **को पूर्णरुपमा जिम्मा लिनेछ।**
- **दोस्रो पक्ष्यले** labor **तथा** material **मा पहिलो पक्ष्यले सिधै** payment **गरिनेछ**, **वा सामान आफै खरिद गर्नसक्नेछ।**

निर्माण कार्यतालिका

क) **पहिलो पक्ष्यले** ले समय तालिका अनुरुप सेवाहरू पूरा गर्नेछ। समापन मिति बाहेक मौसम अवस्था, निर्णय पेन्डिङ वा कुनै पनि महामारीको समयले केहि समय तल वा माथि हुनसक्नेछ ।

ख) साथै कुनै पनि प्रबिधिक समस्या बाहेक, काम मा ढिलाई दुबै पक्ष्य बाट हुने छैन ।

काम सुरु हुने मिति : २०८३/०१/ २१ पूर्ण समापन मिति :२०८४/०१/२१

***(निर्माण मिति प्रकृति, प्राकृतिक प्रकोप, महामारी र चाडपर्वहरू र प्रक्रियाको क्रममा हुने जटिलताहरू अनुसार फरक हुनसक्छ, जुन पहिलो पक्ष्यले ले ग्राहकलाई पहिले नै थाहा दिनेछ ।**

वारेन्टी प्रावधान : सम्झौताहरूले ५ वर्षको लागि संरचनात्मक भाग (सिपेज, पानी चुहावट, सर्ट सर्किट) मा आधारभूत सेवा वारेन्टी प्रदान गर्नेछ । वारेन्टी अवधिमा ग्राहकले **पहिलो पक्ष्यले** *बाहेक कुनै स्थानीय जनशक्ति समावेश समाबेस गर्न पाउने छैन ।*

माथि उल्लेखित नियम र सर्तहरू दुबै पक्षद्वारा निसर्त लागु हुनेछ ।

प्रथम पक्ष	दोश्रो पक्ष
सही :	सही :
नामथर: राजेन्द्र चौधरी	नामथर: **राधिका के.सि.**

Payment Schedule	Installment Amount	Schedule	Percentage	Remarks
Advance Payment / काम सुरु गर्नको लागि	1,863,043.02	१ पटक	15%	
Footing / हात्तीपाहिले सकेको भोलिपल्ट	1,242,028.68	१ पटक	10%	
DPC / डिपिसि सकेको भोलिपल्ट	1,242,028.68	१ पटक	10%	
Ground Floor Wall / **भुइ तल्ला** वालसकेको भोलिपल्ट	1,242,028.68	१ पटक	10%	
Ground Floor Slab / पहिलो ढलान सकेको भोलिपल्ट	1,242,028.68	१ पटक	10%	
First Floor Wall / पहिलो तल्लाको वाल सकेको भोलिपल्ट	1,242,028.68	१ पटक	10%	
First Floor Slab / दोस्रो तल्लाको ढलान सकेको भोलिपल्ट	1,242,028.68	१ पटक	10%	
Second Floor Wall / दोस्रो तल्लाको वाल सकेको भोलिपल्ट	993,622.95	१ पटक	8%	
Second Floor Slab / वाल सकेको भोलिपल्ट	993,622.95	१ पटक	8%	
अन्य बाकी कार्य सहित फिनिशिङ सामन खरिद	1,117,825.81	१ पटक	9%	
Total	12420286.82	११ पटक	100%	

Construction Cost Estimation Summary						
CLIENT'S NAME: Mrs. Radhika K.C. Khadka.						
Address: Tulsipur-8, Doghare, Dang.						
S.N	Description	Unit	Quantity	Rate	Amount	Cum Sum
A	Section 1: Design And Drawing					
1	Municipal Work	Ls			75,000.00	75,000.00
B	Section 2: Levelling and Excavation Works					
1	Excavation works	cft	4,316.52	10.00	43,165.20	90,615.60
2	Back Fill In Excavated Area	cft	3,020.52	10.00	30,205.20	
3	Levelling Works	cft	1724.520	10.00	17,245.20	
C	Section 3: Foundation Protection and Preparation Works					
1	Stone Soiling in Footing and GF Level	sqft	1581.680	35.00	55,358.80	177,939.00
2	PCC Works in Footing and GF Level	cft	395.420	310.00	122,580.20	
D	Section 4: RCC, Reinforcement and Shuttering Works					
1	M20 concrete	cft	3,690.21	455.00	1,679,047.41	4,401,868.62
2	Reinforcement	kg	16,405.84	130.00	2,132,759.13	
3	Shuttering Works	sqft	8429.46	70.00	590,062.08	
E	Section 5: Opening Schedule					
1	Main Door 1	Nos	2.00	80,000.00	160,000.00	924,379.75
1	Main Door 2					
a.	Main Door2 (3"x4") Frame (wooden)	Nos	0.00	8,000.00	-	
b.	Shutter	Nos	0.00	4,500.00	-	
c.	Main Door2 Lock+Handel	Nos	0.00	3,000.00	-	
2	Internal Doors					
a.	3"x4" Frame(wooden) Frame	Nos	21.00	8,000.00	168,000.00	
b.	Shutter ReadyMade	Nos	21.00	3,500.00	73,500.00	
c.	Lock,With Necessary Installation	Nos	21.00	2,000.00	42,000.00	
3	Windows (UPVC)	sqft	573.50	750.00	430,125.00	
a.	Metal Work in Window Ground Floor only	sqft	191.17	265.50	50,754.75	
F	Section 6: Walls / Plasters/Painting					
1	Brick Masonary	cft	3,678.49	450.00	1,655,321.81	3,479,637.05
2	Plaster Works	sqft	12,772.35	80.00	1,021,787.84	
3	Painting Works	sqft	16,431.49	40.00	657,259.52	
a.	Internal Wall Putting	sqft	10352.79	10.00	103,527.89	
b.	Enamel Paint in Door and Metal Work	sqft	1043.50	40.00	41,740.00	
G	Section 7: Tiles ,Marble,Screeding ,Punning and Granite					
1	Screeding	sqft	3,141.16	50.00	157,058.00	901,757.33
2	Granite Work	sqft	177.57	510.00	90,562.83	
3	Granite work in Staircase	sqft	630.69	510.00	321,651.90	
4	Tile in living, G.F. Kitchen, F.F. Kitchen Office room	Sqft	1,583.26	210.00	332,484.60	
5	Parqueting in first floor kitchen	Sqft	0.00	650.00	-	
H	Section 8 : Exterior Design Section					
1	Parking Tile work	Sqft	0.00	210.00	-	0.00
I	Section 9: Skill Special treatment and waterproofing works					
1	Membrane Sheet layering	sqft	812.51	110.00	89,376.20	89,376.20
2	PMM insertion	sqft	0.00	30.00	-	
3	2K Coating Treatment	sqft	812.51	30.00	-	
4	Zero Side Polymer Coating Treatment	sqft	0.00	30.00	-	
5	Anti Crack Seal	LS	1		-	
J	Others Items					
1	Overhead Watertank and Metal Stand					669,132.79
a.	Tank 1000 Ltr-2 Nos	Nos	2	15,000.00	30,000.00	
b.	Metal Stand	Nos	1	28,000.00	28,000.00	
2	Underground Water tank (8000 Ltr)	TS			109,601.04	
3	Railling (Stairs) SS Steel	Rft	77.59	1,250.00	96,987.50	
4	Railing Balconey (Toughned Glass)	Rft	62.59	1,350.00	84,496.50	
5	Railing on Terrace (Toughned Glass)	Rft	0.00	1,350.00	-	
6	Metal Staircase	LS	1		30,000.00	
7	Septic Tank and Soak Pit	TS	1		125,047.75	
8	Design Cost	LS	1		150,000.00	
9	Earthing	LS	1		15,000.00	
				Internal Furnishing	-	
				Sub - Total	10,809,706.34	
				Electrical fittings	432,388.25	
				Sanitary pipes and fittings	586,750.00	
				Total including Management Charge	12,420,286.82	
				Contract Agreement Amount	12,420,286.82	
				Internal Furnishing		

Sanitary / Bathroom Fitting					
S.N.	**Description**	**Unit**	**Rate**	**Amount**	**Remark**
1	**Wash basin**				
	Wash Basin : 1 Set Per Bathroom	1	4,800.00	4,800.00	
2	**Commode**				
	Commode : 1 Set Per Bathroom	1	18,500.00	18,500.00	
3	**Wall Mixture**				
	All Floor Wall Mixture : 1 Set Per Bathroom	1	6,800.00	6,800.00	
4	**C- Tap Mixture Mixture**				
	All Floor As necessary	1	4,500.00	4,500.00	
5	**CP Set :** As Feeting Nacessary	1	4,500.00	4,500.00	
6	**Angle Valve :** As Feeting Nacessary				
	Per Bathroom Nacessary	4	850.00	3,400.00	
7	**Commod Spray :** Per Bathroom 1 set	1	1,550.00	1,550.00	
8	**Mirror :** Per Bathroom 1 Set	1	1,100.00	1,100.00	
9	Other Necessary fitting iteam	Ls	8,000.00	8,000.00	
		Sub-Total		**53,150.00**	
		Per Bathroom Set - 53150			
	Total No of Bathroom	**5**			
	Wash Basin	**0**	**4800**	**-**	
	Toilet Pan	**1**	**3000**	**3,000.00**	
1	**Sink**	**1**	**4000**	**4,000.00**	
2	**Mixture**	**1**	**8000**	**8,000.00**	
		Sub-Total		**12,000.00**	
	No of Kitchen	**2**		**24,000.00**	
		Sub-Total	**Sub-Total**	**316,750.00**	
10	Buying And Installation of Pipe and Fitting			**222,500.00**	
11	Necessary Cost For Installation			**62,500.00**	
		Total Cost		**586,750.00**	

Note:
1. सम्पूर्ण कार्य हरु दक्ष्य कामदारहरु बाट सम्पन गरिने छ ।
2. घर धनी ले इच्छायको खण्डमा ,आपसी समझ्दारिमा (सामान परिवर्तन गर्न साकिने छ ।
3.(ब्रन्ड)कम्पनिको सामन परिवर्तन हुँदा सामान को मुल्यमा पनि परिवर्तन हुने छ ।
4. आपसी सहमतिमा मात्र कार्य परिवर्तन गर्न पाहिने छ ।

Section1. Preliminary consultation upto Naksa Pass

S.no	Description	unit	Nos	Length	Breadth	Height	QUANTITY
A	**Site Visit site measurement and first phase consultation**						
1	Site Visit and Measurement	NOs					
2	Conceptual Draft	NOs	1.00				1.00
3	2D of each floors	NOs	1.00				1.00
4	3D preparation	NOs	1.00				1.00
5	Estimation and Financial Analysis	NOs	1.00				1.00
B	**Municipal Drawing Preparation and Naksa Pass**						
1	Municipal Drawing Preparation and Naksa Pass	Nos	1.00				1.00

Section2 . Preparatory Works

S.no	Description	unit	Nos	Length	Breadth	Height	QUANTITY
A	**Site Visit site measurement and first phase consultation**						
1	Site Clearance	NOs					
2	Construction of LAbour Camp	NOs	1.00				1.00
3	Installation and fixing of CCTV around the construction areas	NOs	1.00				1.00

Section 3 Levellling and Excavation Works

S.no	Description	unit	Nos	Depth	Volume						
A	**Levelling Works**										
	Levelling Works	1	LS								
B	**Excavation Works**					Back fill	Backfilling Be				
S.no	Description	Area of Footing	Nos	Depth	Volume	Volume	Discription	l	b	h	vol
1	Excavation for footing										
	Footing	432.00	1	6	2592	1296					
	Soil Buy	1149.68	1	1.5	1724.52	862.26					
					0	0					
				Total	4316.520	1296				Total	0
Total Volume to excavate From original ground level			4316.520	cuft							
Total Back Fill	1296	cuft									
Soil Cutting	1724.52	cuft									
	3020.52	cuft									

Section 4 Foundation Preparation Works

S.no	Description	unit	Nos	Depth	Volume	
A	**Protection Works**					
	Necessary arrangements of sheet piling for protection works	1	LS			
B	**Soil Compaction Works**					
	Necessary compaction works in foundation	1	LS			
C	**Stone Soiling and PCC in Foundation**					
1	**Preparation in foundation**	**NOs**	1			
S.N	**Footing Description**	**Area of Footing**	**NO.**	**Thickness**	**Brick Soling (cft)**	**PCC Works(cft)**
1	**Total Area for working**	432.00	1	0.666666667	288	108
2						
				Total	288	108
Brick Soiling			288.000	cft		
PCC Works			108.000	cft		
D	**Stone Soiling and PCC in GF**					
1	**Necessary compaction works before performing PCC in GF**	1	LS			
S.N	**Description**	**Area**	**Nos.**	**Thickness**	**Brick Soling(cft)**	**Pcc Work(cft)**
1	**Total Area for working**	1149.68	1	0.666666667	766.4533333	287.42
				Total	766.4533333	287.42
Brick Soiling			766.453	cft		
PCC Works			287.420	cft		

Footing Estimator

S.N	Footing Description	Area of Footing	Perimeter	Thickness						Total		
Instruction to the estimators	Visualize the footing type with dimension from structural drawing	Calculate the area of footing from AutoCAD	Measure Perimeter of footing from AutoCAD	Obtain the thickness from structural drawing		Nos.				Total Volume (Calculated Automatically)	Total Area	Total Area for Formwork (Calculated)
1	F1	25	20. 00	1. 67		0. 00				0. 00	0. 00	0. 00
2	F2	36	24. 00	1. 67		12. 00				720. 00	432. 00	480. 00
3	F3	30. 25	22. 00	1. 67		0. 00				0. 00	0. 00	0. 00
4	F4	42. 25	26. 00	1. 67		0. 00				0. 00	0. 00	0. 00
5	F5	49	28. 00	1. 67		0. 00				0. 00	0. 00	0. 00
6	Mat Foundation	921	93. 60	1. 67		0. 00				0. 00	0. 00	0. 00
	Total					12.00				720.00	432.00	480.00

Column Estimator

Discription	Sectional Area	Height	Area	Nos		VOL(cuft)				Area(sqft)	No of storey
Up To Plinth											
C1	1.36	5.00	4.67	12.00		81.67				280.00	
		IN CASE, DPC height needs to be increased estimator needs to consult with Field Surveyor									
Up To Top											
C1	1.36	8.75	4.67	40.00		476.39				1633.33	
In Terrace											
C1	1.36	3.00	4.67	12.00		49.00				168.00	
				Total		607.06				1913.33	

Slab Estimator

Discription	Slab Area(sqft)	Thickness	Total Volume(cft)	Area For formwork(sqft)
Ground Floor	1149.680	0.417	479.033	1149.680
First Floor	1200.000	0.417	500.000	1200.000
Second Floor	1024.650	0.417	426.938	1024.650
Third Floor	284.810	0.417	118.671	284.810
Fourth Floor	0.000	0.417	0.000	0.000
Fifth Floor	0.000	0.417	0.000	0.000
Top Floor	0.000	0.417	0.000	0.000
STAIRCASE	0.000	0.417	0.000	0.000
		Total	1524.64	3659.14
	1954.456			

Beam Estimator

S.N	Strap Beam	Lower Tie Beam	Upper Tie Beam	Ground Floor Beam	First Floor Beam	Second Floor Beam	Third Floor Beam	Fourth Foor Beam	Fifth Floor	Stair Secondary	Top Floor
Size	12	9	9	9	9	9	9	0	0	0	0
	16	9	9	9	9	9	9	0	0	0	0
Section	1.333	0.563	0.563	0.563	0.563	0.563	0.563	0.000	0.000	0.000	0.000
Length Along Y Axis											
	44.730	163.400	208.130	208.130	208.130	208.130	50.570	0.000	0.000	0.000	0.000
Volume	59.640	91.9125	117.073125	117.073125	117.073125	117.073125	28.445625	0	0	0	0
Area	119.280	245.100	312.195	312.195	312.195	312.195	75.855	0.000	0.000	0.000	0.000

Beam Total	648.291	cuft
Formworks	1689.015	sqft

Shear Wall Estimator

Grid	Thickness	Height	Length	Nos		Volume				Area
	0.750	9.33	86.1	0		0.00				1606.63
				Total		0.00				

Sill Band and Lintel Band Estimator

Discription	Length	Breadth	Thickness	Volume		Area
Ground Floor	110.320	0.75	0.25	41.37		110.32
	89.350	0.333	0.25	14.89		89.35
First Floor	123.650	0.75	0.25	46.37		123.65
	102.350	0.333	0.25	17.06		102.35
Second Floor	105.750	0.750	0.25	39.66		105.75
	97.620	0.333	0.25	16.27		97.62
Third Floor	22.990	0.75	0.25	8.62		22.99
	35.940	0.333	0.25	5.99		35.94
Fourth Floor	0.000	0.75	0.25	0.00		0.00
	0.000	0.333	0.25	0.00		0.00
Fifth Floor	0.000	0.75	0.25	0.00		0.00
	0.000	0.333	0.25	0.00		0.00
Top Floor	0.000	0.75	0.25	0.00		0.00
	0.000	0.333	0.25	0.00		0.00
Upper + Lower Terrace	0.000	0.333	0.25	0.00		0.00
			Total	**190.23**		**687.97**

Summary

S.N	Description	Qty (cuft)	Formworks (sqft)		Remarks
A	Footing	720.00	480.00		
B	Beams	648.29	1689.02		
C	Columns	607.06	1913.33		
D	Slabs	1524.64	3659.14		
F	Sill and Lintel	190.23	687.97		
	Total	3690.21	8429.46		
E	Shear Walls	0.00	0.00		

Reinforcement Work			Reinforcement For Shear Wall						
2% of RCC	73.804	ft3	1.50% of RCC FOR SHEAR WALL		0.000				ft3
	2.090	m3			0.000				m3
	16405.839	kg			0.000				Kg

Reinforcement Total 16405.84 Kg

Section 6 Doors Windows and Opening Schedule

Paste the opening Schedule

S.N	Description	Associated Wall thickness	N0	L	B	H	Area(sqft)	Deduction in Brick Masonary Walls (cft)	Deduction in wall plasters (sqft)	Deduction in Paintings (sqft)
	DOOR									
1	**MAIN DOOR MD1**	**0.750**	**2**	**4.000**	**1.000**	**8.000**	**64.000**	48	128	128
2	**MAIN DOOR MD2**	**0.750**	**0**	**3.000**	**1.000**	**8.000**	**0.000**	0	0	0
3	**D1**	**0.750**	**1**	**3.000**	**1.000**	**7.000**	**21.000**	15.75	42	42
4	**D2**	**0.417**	**10**	**3.000**	**1.000**	**7.000**	**210.000**	87.5	420	420
5	**D3**	**0.750**	**0**	**5.000**	**1.000**	**7.000**	**0.000**	0	0	0
6	**D4**	**0.750**	**2**	**2.500**	**1.000**	**7.000**	**35.000**	26.25	70	70
7	**D5**	**0.417**	**8**	**2.500**	**1.000**	**7.000**	**140.000**	58.333333	280	280
	WINDOW						470.000			
1	**RS**	**0.750**	**0**	**12.800**	**1.000**	**8.400**	**0.000**	0	0	0
2	**W1**	**0.750**	**6**	**6.000**	**1.000**	**5.000**	**180.000**	135	360	360
3	**W2**	**0.750**	**6**	**5.000**	**1.000**	**5.000**	**150.000**	112.5	300	300
4	**W3**	**0.750**	**1**	**4.000**	**1.000**	**5.000**	**20.000**	15	40	40
5	**V2**	**0.750**	**2**	**2.000**	**1.000**	**4.000**	**16.000**	12	32	32
6	**V3**	**0.750**	**1**	**3.000**	**1.000**	**5.000**	**15.000**	11.25	30	30
7	**v4**	**0.750**	**7**	**2.000**	**1.000**	**3.000**	**42.000**	31.5	84	84
8	**v5**	**0.750**	**1**	**1.500**	**1.000**	**3.000**	**4.500**	3.375	9	9
8	**W5**	**0.417**	**1**	**4.000**	**1.000**	**5.000**	**20.000**	8.3333333	40	40
9	**W6**	**0.750**	**0**	**9.500**	**1.000**	**3.000**	**0.000**	0	0	0
10	**W7**	**0.750**	**0**	**6.000**	**1.000**	**20.000**	**0.000**	0	0	0
11	**W8**	**0.750**	**0**	**5.400**	**1.000**	**4.600**	**0.000**	0	0	0
12	**W9**	**0.750**	**0**	**5.100**	**1.000**	**4.600**	**0.000**	0	0	0
13	**W10**	**0.750**	**0**	**5.000**	**1.000**	**7.000**	**0.000**	0	0	0
14	**W11**	**0.750**	**0**	**4.000**	**1.000**	**5.000**	**0.000**	0	0	0
15	**W12**	**0.750**	**0**	**4.000**	**1.000**	**4.600**	**0.000**	0	0	0
16	**W13**	**0.750**	**0**	**3.600**	**1.000**	**4.600**	**0.000**	0	0	0
17	**W14**	**0.750**	**0**	**3.300**	**1.000**	**7.000**	**0.000**	0	0	0
18	**W15**	**0.417**	**0**	**3.000**	**1.000**	**4.600**	**0.000**	0	0	0
19	**W16**	**0.750**	**0**	**2.000**	**1.000**	**3.600**	**0.000**	0	0	0
20	**W17**	**0.750**	**0**	**9.700**	**1.000**	**8.000**	**0.000**	0	0	0
21	**W18**	**0.417**	**0**	**8.300**	**1.000**	**1.000**	**0.000**	0	0	0
19	**SD1**	**0.750**	**3**	**6.000**	**1.000**	**7.000**	**126.000**	94.5	252	252
20	**SD2**	**0.417**	**0**	**4.000**	**1.000**	**7.000**	**0.000**	0	0	0
21	**V1**	**0.417**	**0**	**3.000**	**1.000**	**3.000**	**0.000**	0	0	0
				114.500			**573.500**			
							Total	659.29167	2087	2087

Summary

S.N	Description	Nos	Area of panel	Length of frame	Volume of Frame
					3"*4"
1	Main Doors (Wood)	2.000	64.000	48.000	4
2	Internal Doors (Wood)	21.000	406.000	#REF!	#REF!
4	Windows (upvc)	28.000	573.500		
			0.000		

Section 7 Wall Plaster and Painting Estimation

S.N	Description	unit	Nos	Length	Breadth	Height	Brick Masonary Volume
A	Brick Masonary Walls						
a	Under the plinth (Toe Walls)	nos					
1	Total walls area from cad	cft		115.90		5.00	579.49
b	Ground floor Walls						
1	Total walls area from cad 9"	cft	1.00	82.74		8.75	723.98
2	Total walls area from cad 4"	cft	1.00	37.26		8.75	326.02
c	First Floor Wall						
1	Total walls area from cad 9"	cft	1.00	92.7375		8.75	811.45
2	Total walls area from cad 4"	cft	1.00	42.68		8.75	373.45
d	Second Floor Wall						
1	Total walls area from cad 9"	cft	1.00	79.3125		8.75	693.98
2	Total walls area from cad 4"	cft	1.00	40.70754		8.75	356.19
e	Third Floor Wall						
1	Total walls area from cad 9"	cft	1.00	17.2425		8.75	150.87
2	Total walls area from cad 4"	cft	1.00	14.98698		8.75	131.14
f	Fourth Floor Wall						
1	Total walls area from cad 9"	cft	1.00	0		8.75	0.00
2	Total walls area from cad 4"	cft	1.00	0		8.75	0.00
g	Fifth Floor Wall						
1	Total walls area from cad 9"	cft	1.00	0.00		8.75	0.00
2	Total walls area from cad 4"	cft	1.00	0.00		8.75	0.00
g	Top Floor Wall						
1	Total walls area from cad 9"	cft	1.00	0.00		8.75	0.00
2	Total walls area from cad 4"	cft	1.00	0.00		8.75	0.00
d	Parapet Walls						
1	Varahanda	cft	1.00	29.88		0.23	6.87
2	Upper Terrace	cft	1.00	16.19		3.00	48.58
3	Lower Terrace	cft	1.00	45.26		3.00	135.77
							191.22

Summary

S.N	Description	Brick Masonary (cft)	Plaster	Paint
1	Toe Wall	579.49	14859.35	18518.49
2	Ground floor	1,049.99		
3	First Floor	1,184.90		
4	Second Floor	1,050.18		
5	Third Floor	282.01		
4	Fourth Floor	0.00		
5	Fifth Floor	0.00		
6	Top Floor	0.00		
7	Parapet walls	191.22		
8	Deduction for Shutter	0.00	0.00	0.00
8	Deduction from opening schedule	659.2916667	2087	2087
	Total	3,678.49	12772.35	16431.49

External

	L	H	A(Sqft)
GF	199.67	8.75	1747.11
FF	226.00	8.75	1977.50
SF	203.37	8.75	1779.49
TF	58.93	8.75	515.64
Fourth Floor	0.00	8.75	0.00
Fifth Floor	0.00	8.75	0.00
Top Floor	0.00	8.75	0.00
Lower Parapet	108.53	3	325.59
Upper Parapet	38.83	3	116.49
Varahanda	71.66	0.23	16.48
Deduction in zero side	0.00	20.5	0.00
		Total	6478.30

Internal Walls				RFF	
				Celling	Beam
	L	H	A(Sqft)	A(Sqft)	A(Sqft)
GF	199.67	9.50	1896.87	1149.68	1687.4
FF	226.00	9.50	2147.00	1200	
SF	203.37	9.50	1932.02	1024.65	
TF	58.93	9.50	559.84	284.81	
Fourth Floor	0.00	9.50	0.00	0	
Fifth	0.00	9.50	0.00	0	
Top Floor	0.00	9.50	0.00	0	
Staircase	0	9.50	0.00	0	
Lower Parapet	108.53	3	24.96		
Upper Parapet	38.83	3	116.49		
Varahanda	71.66	0.23	16.48		
		Total	6693.65		
	TOTAL		13171.948	3659.14	1687.4

Screeding , Punning , Tiles , Marbles , Granite , Parqueting

S.no	Description	unit	Nos	Length	Breadth	Area	Tiles(sqft)	Marble(sqft)	Granite(sqft)	Parqueting (sqft)	2 inch Screeding(sqft	Punning(sqft)
A	**Ground Floor**											
1	Bedroom 1		1.00			123.84					123.84	
2	Bedroom 2		1.00			133.10					133.10	
3	Bedroom 3		1.00			132.77					132.77	
4	Kitchen/Dining		1.00			155.26	155.26				155.26	
B	**First Floor**											
1	M. Bedroom		1.00			155.05					155.05	
2	Bedroom		1.00			148.05					148.05	
3	Kitchen/Dining		1.00			174.52	174.52				174.52	
4	Living room		1.00			159.46	159.46				159.46	
5	Store		1.00			19.15					19.15	
6	Balconey 1		1.00			68.11					68.11	
7	Balconey 2		1.00			29.91					29.91	
8	Balconey 3		1.00			34.21					34.21	
9	Passage		1.00			184.74					184.74	
C	**Top Floor**											
1	Bedroom 1		1.00			131.91					131.91	
2	Bedroom 2		1.00			136.22					136.22	
3	Office Room		1.00			96.08					96.08	
4	Puja Room		1.00			23.02					23.02	
5	Passage		1.00			140.52					140.52	
D	**Top Floor**											
1	Laundry		1.00			36.04	36.04				36.04	
E	**Lower Terrace**											
1	Floor		1.00			776.22					776.22	
2	Skirting		1.00			108.53						
E1	**Upper terrace**											
1	Floor		1.00			282.98					282.98	
2	Skirting		1.00			38.83						
F	**Granite Work on Window Base**											
	Total Lenght of Window		1.00	114.50	1.08	0.00			0.00			
	Lower Terrace		1.00	108.53	1.08	117.57			117.57			
	Upper Terrace		1.00	38.83	1.08	0.00			0.00			
G	**Staircase**											
	(With Nosing)(Double Moulding)											
1	Risers		18			216			216.00			
2	Trades		15			180			180.00			
3	Landing		2			142.02			142.02			
4	Skirting		1			92.67			92.67			
						630.69						
H	**Kitchen**											
1	Rental Kitchen		0.00			0.00			0.00			
2	Personal Kitchen		0.00			60.00			60.00			
I	**Bathrooms**											
1	**Ground Floor**											
a	**Common T/B**											
	Floor		**1.00**			**21.08**	**21.08**					
	Wall		**1.00**			**130.62**	**130.62**					
b	**Common T/B**											
	Floor		**1.00**			**31.52**	**31.52**					
	Wall		**1.00**			**164.36**	**164.36**					
2	**First Floor**											
a	**Common T/B**											
	Floor		**1.00**			**50.88**	**50.88**					
	Wall		**1.00**			**221.58**	**221.58**					
b	**Attach T/B**											
	Floor		**1.00**			**39.91**	**39.91**					
	Wall		**1.00**			**191.24**	**191.24**					
3	**Second Floor**											
a	**Common T/B**											
	Floor		**1.00**			**38.73**	**38.73**					
	Wall		**1.00**			**168.06**	**168.06**					
b	**Attach T/B**											
	Floor		**1.00**			**0.00**	**0.00**					
	Wall		**1.00**			**0.00**	**0.00**					
						1,036.90						
J	**Parking Tiles**											
	Parking Tiles		**1.00**			**0.00**	**0.00**					
	Total						1,583.26	0.00	808.26	0.00	3,141.16	0.00

Summary

S.N	Description	Area(sqft)
1	Tiles Works	1,583.26
2	Granite Works	808.26
3	Marble Works	0.00
4	Screeding	3,141.16
5	Punning	0.00
6	Parqueting Works	0.00

Section 9 Special Treatment and Waterproofing

S.no	Description	unit	Nos	Length	Breadth	Area
A	**At Plinth Beam**					
	Provision of Bituminous	**sqft**	**1.00**	**208.13**	**0.75**	**156.10**
B	**At Bathroom Floors**					
	Provision of	**sqft**				**373.43**
C	**At Terrace Floors**					
	Provision of	**sqft**				**282.98**
D	**At Construction Joint**					
	Application of Bituminous	**sqft**				**0.00**
D	**At Zero Side Punning Walls**					
	Provision of PMM Mortar	**sqft**	**1.00**	**0.00**	**20.50**	**0.00**

Summary of Works

S.N	Description of works	Quantity
1	Membrane Sheet layering	812.51
2	PMM insertion	0.00

Section 10 Railing Works

S.no	Description	unit	Steel	Wood	Toughned Glass	Iron
A	**Staircase**					
	Provision of Railing in staircase	**Rft**	**56.22**			
B	**At Balcony**					
	Provision of Railing in Balcony	**RFT**	**21.37**		**62.59**	
B	**At Lower terrace**					
	Provision of railing	**RFT**	**0.00**			
D	**At Upper terrace**					
	Provision of railing	**RFT**	**0.00**			

Summary of Works

S.N	Description of works	Quantity	Unit
1	SS Steel Railing	77.59	Running Feet
2	MS Railing		
3	Wooden Railing	0.00	
4	Toughned glass Railing	62.59	

UNDER GROUND WATER TANK INTERNAL

S,N	Description of work	unit	no	Length	Breadth	height	qty (cu.ft)
1	Earth work	cu.ft	1	5	7	5	175
2	Soling work	sq.ft	0	5	7	0.21	7.29
3	Pcc work	cu.ft	0	5	7	0.21	7.29
4	Shorter Shear wall	cuft	2	7	0.5	5	35.00
5	Longer Shear Wall	cu.ft	2	5	0.5	5.00	25.00
6	Base Slab	cuft	1	5	7	0.33	11.67
7	Top Slab	cuft	1	5	7	0.33	11.67
8	Reinforcement	cuft					1.25
		cum					0.04
		kg					277.86
9	Slab Cover (Iron)	Per pie	1				

S.N	Description of work	unit	no	Qty (m)	Rate	Amount	Remarks
1	Earth work	cu.ft	1	175	23	4025	
2	soling work	sq.ft	1	7.29	68	495.8333333	
3	pcc work	cu.ft	1	7.29	360	2625	
4	SHEARWALL RCC WORK	cu.ft	1	83.33	550	45833.33	
5	REINFORCEMENT WORK	KG	1	277.8605625	130	36121.87313	
6	Plaster Work	sq.ft	1	200	85	17000	
7	CAP	PIC	1	1	3500	3500	
					Total	**109601.0398**	

SOAK PIT

S,N	Description of work	Unit	No	Length	Breadth	height	qty (cu.ft)
1	Earth work	cu.ft	1	2	2	4	16
2	soling work	sq.ft	0	0	0		0
3	pcc work	cu.ft	0	0	0	0	0
4	BRICK WORK UP TO GROUND	cu.ft	1	2	2	4	16
5	RCC WORK	cuft	1	2	2	0.33	1.32
6	REINFORCEMENT	KG	1				11
7	PIPE (2 PIC 6 INCH)	PIC	2				2

S.N	Description of work	unit	Qty (ft)	Qty (m)	Rate	Amount	Remarks
1	Earth work	cu.ft	16	0.453129425	721	326.7063155	
2	soling work	sq.ft	0	0	750	0	
3	pcc work	cu.ft	0	0	15747	0	
4	BRICK WORK UP TO GROUND	cu.ft	16	0.453129425	15000	6796.941376	
5	RCC WORK	cuft	1.32	0.037383178	17944.56	670.8246729	
6	REINFORCEMENT	KG	11		130	1430	
7	PIPE (2 PIC 6 INCH)	PIC	2		4000	8000	
					Total	15794.47236	

Septic Tank

S,N	Description of work	Unit	No	Length	Breadth	height	qty (cu.ft)
1	Earth work	cu.ft	1	4	4	5	80
2	soling work	sq.ft	1	4	4	5	16
3	pcc work	cu.ft	1	4	4	5	80
4	BRICK WORK UP TO GROUND	cu.ft	1	5	4	7	140
5	RCC WORK	cuft	1	5	4	0.33	6.6
6	REINFORCEMENT	KG	1				11
7	PIPE (2 PIC 6 INCH)	PIC	2				2

S.N	Description of work	unit	Qty (ft)	Qty (m)	Rate	Amount	Remarks
1	Earth work	cu.ft	80	2.265647125	721	1633.531577	
2	soling work	sq.ft	16	1.486988848	750	1115.241636	
3	pcc work	cu.ft	80	2.265647125	15747	35677.14528	
4	BRICK WORK UP TO GROUND	cu.ft	140	3.96488247	15000	59473.23704	
5	RCC WORK	cuft	6.6	0.186915888	17944.56	3354.123364	
6	REINFORCEMENT	KG	11		130	1430	
7	PIPE (2 PIC 6 INCH)	PIC	2		4000	8000	
					Total	109253.2789	

Quotation of Material		
S.N	**Material Name**	**Material Quality / Works Description**
1.	Cement	Sona Cement / Sagarmatha Cement (If Shortage Same quality cement will be used)
2.	Rebar (Dandi)	Laxmi Steel / Narayani Steel (If Shortage Same quality rebar will be used)
3.	Baluwa (Sand)	Double washed
4.	Gitti (Aggregate)	Crushed Aggregate
5.	Windows	UPVC/Wooden
6.	Chaukosh	Nepali Agrakh wood/Indian Agrakh Wood/Chilaue
7.	Room Doors	Ready Made (Ply Khapa)
8.	Main Door	Dela Khapa
9.	Wall 9"	Below GL and Exterior wall
10.	Wall 4"	Inner Partition / (According to Design)
11.	Granite	For Stair, Kitchen Slab and Window base (Price Up to Nrs. 250 Per sq.ft)
12.	Tiles	Kitchen Floor / Toilet and Living (Price Up to NRs. 120 per sq.ft)
13.	Toilet and Bathroom	According Sanitary Specification
14.	Pipes	According Sanitary Specification
15.	Electrical Points	According Electrical Specification
16.	Electrical Bulbs	According Electrical Specification
17.	Electrical Switch	According Electrical Specification
18.	Paint and putting	Inner Putting with Paint, Exterior Paint Only (Asian Paint)
19.	Water Tank	Nepatop 1000 Ltrs With Metal Stand

Note:

१. सम्पूर्ण कार्यहरु दक्ष कामदारहरु बाट सम्पन गरिने छ ।

२.(ब्राण्ड) कम्पनिको सामान परिवर्तन हुँदा सामान को मुल्यमा पनि परिवर्तन हुने छ ।

३. आपसी सहमतिमा मात्र कार्य परिवर्तन गर्न पाहिने छ ।

ELECTRICAL SPECIFICATION	
OWNER'S NAME: Mrs. Radhika K.C. Khadka.	
S.N.	**Description**
1	Wires : Litmus Cable or equivalent
2	Accessories: CG / Swift Gold or equivalent
3	Per Bedroom Specification 1 Wall light /4 ceiling light (Dome light)/ 2 Power Socket /3 Way Gang Switch
4	Per Living room Specification Dual wall light /dual ceiling light (Dome light) / 2 power socket /3 way gang switch
5	Per Bathroom room specification Mirror light /dual ceiling light (Dome light)/ / 2 power socket /3 way gang switch
6	3 DB box per floor / 1 MCB Box
7	Per Kitchen specification /Dual Ceiling Light (Dome Light)/ 3 power socket /3 way gang switch
8	Exterior Single dome light in each balcony top
9	Power socket 7/22 in Underground tank and inar each
10	Pair of light on Entrance Gate
11	Single Dome Light with switch in each staircase
12	Each Dome Light in each passage
13	4 dome light in lower terrace

Note:

१. सम्पूर्ण कार्यहरु दक्ष कामदारहरु बाट सम्पन गरिने छ ।

२.(ब्राण्ड) कम्पनिको सामान परिवर्तन हुँदा सामान को मुल्यमा पनि परिवर्तन हुने छ ।

३. आपसी सहमतिमा मात्र कार्य परिवर्तन गर्न पाहिने छ ।